
# LABC Registered Construction Details Masonry



### **Registration Number: E5MCFF22**



#### **Build Up**

**External Masonry Cavity Wall** 

Masonry Outer Leaf ( $\lambda = 0.77$ )

100mm Aircrete Block Inner Leaf ( $\lambda = 0.11 \text{ W/mK}$ )

**Full Fill Insulation** 

In Situ Ground Bearing Concrete Floor

100mm Insulation Below Slab (0.022W/mK)









## LABC Registered Construction Details Masonry



### Calculated ψ-values

	Inner leaf blockwork
	Aircrete Block λ = 0.11 W/mK
<b>Cavity Insulation</b>	ψ-value W/mK
<b>100mm</b> λ=0.037	0.080
150mm λ=0.037	0.070
<b>100mm</b> λ=0.032	0.077
150mm λ=0.032	0.068

#### **Points to Watch**

- Ensure cavities are kept clean of mortar snots and other debris during construction
- Damp proof membrane / air barrier should be lapped to damp proof course and plaster stop bead.
- Any service penetrations through the damp proof membrane / air barrier should be suitably sealed.
- The wall insulation installed must be considered fit for purpose below the wall dpc in relation to water absorption.







