


# LABC Registered Construction Details

## Masonry



Registration Number: E5MCFF23



### Build Up

External Masonry Cavity Wall

Masonry Outer Leaf ( $\lambda = 0.77$ )

100mm Aircrete Block Inner Leaf ( $\lambda = 0.15 \text{ W/mK}$ )

Full Fill Insulation

In Situ Ground Bearing Concrete Floor

100mm Insulation Below Slab ( $0.022\text{W/mK}$ )



## Calculated $\psi$ -values

Cavity Insulation	Inner leaf blockwork
	Aircrete Block $\lambda = 0.15$ W/mK
	$\psi$ -value W/mK
100mm $\lambda=0.037$	0.087
150mm $\lambda=0.037$	0.077
100mm $\lambda=0.032$	0.084
150mm $\lambda=0.032$	0.075

## Points to Watch

- Ensure cavities are kept clean of mortar snots and other debris during construction
- Damp proof membrane / air barrier should be lapped to damp proof course and plaster stop bead.
- Any service penetrations through the damp proof membrane / air barrier should be suitably sealed.
- The wall insulation installed must be considered fit for purpose below the wall dpc in relation to water absorption.

# LABC Registered Construction Details Masonry



### Registered Construction Details Worksheet

<b>Project</b>	<b>Date</b>

<b>Designer</b>

**Assessment Stage**

<b>SAP Assessor Name</b>	<b>Date verified</b>

**Build Stage**

<b>Builder</b>	<b>Date Installed</b>

**Inspection Stage**

<b>Checked By</b>	<b>Date Inspected</b>

Thermal Specification	Required λ value
Outer Leaf	
Cavity Insulation	
Inner Leaf	
Internal finish	
Floor Insulation	
Perimeter Insulation	
Roof Insulation	
Cavity Closer	
Windows	
Doors	

Product Specified	Stated λ Value

### Applicable Detail Reference Numbers used

Reference No	Description	Stated Ψ Value from Table W/mK	Default Ψ W/mK	F Value From Table
e.g. E5 MFF 1	Suspended beam and block floor – 100mm Insulation below screed External wall	0.056	0.16	0.921

