
# LABC Registered Construction Details Masonry



### **Registration Number: E5MCPF1**



#### **Build Up**

**External Masonry Cavity Wall** 

Masonry Outer Leaf ( $\lambda = 0.77$ )

Ultra Lightweight Concrete Block  $\lambda \le 0.28 \text{ W/Mk}$ 

Partial Fill Insulation

Beam and Block Floor

Lightweight Floor Block

100mm Insulation Below Screed (0.022W/mK)









# LABC Registered Construction Details Masonry



### Calculated ψ-values

	Inner leaf blockwork
	Ultra Lightweight Concrete Block λ ≤ 0.28 W/mK
Cavity Insulation	ψ-value W/mK
50mm λ=0.022	0.055
100mm λ=0.022	0.056

#### **Points to Watch**

- Ensure cavities are kept clean of mortar snots and other debris during construction
- Damp proof membrane / air barrier should be lapped to damp proof course and plaster stop bead.
- Any service penetrations through the damp proof membrane / air barrier should be suitably sealed.
- Sub floor ventilation to be in accordance with manufacturers recommendations. A cavity barrier type sleeve should be used through the cavity.
- The wall insulation installed must be considered fit for purpose below the wall dpc in relation to water absorption.







